



HAYWOOD COUNTY SCHOOLS

MAINTENANCE
401 Farmview Drive, Waynesville, NC 28786
P: 828.456.2402 | F: 828.456.2452

Maintenance Director: Josh Mease

ADDENDUM #1

May 14, 2020

TO: ALL POTENTIAL BIDDERS
FROM: JOSH MEASE, MAINTENANCE DIRECTOR
SUBJECT: CENTRAL OFFICE ANNEX BUILDING ROOF REPLACEMENT

(RFP# 5-20)

The following specifications are hereby made a part of the original documents. Bidders shall acknowledge receipt of this addendum by notation in the space provided on the Proposal Form.

Addendum includes: Information discussed during pre-bid.

Addendum #1

RFP# 5-20



ADDENDUM to RFP# 5-20

Central Office Annex Building Roof Replacement

Include:

- Install 1½" ISO insulation on entire roof area.
- Install twenty (20) one-way air vents.
- Install metal cap 53 ½" x 58½" over chimney.
- Install metal cover 58½" x 86" x 6" thick over chimney.

NOTE:

New part of building has rubber membrane, ½" wood fiber board, built up tar and gravel and gyp deck

Old roof has rubber membrane, wood fiber board, eps board, built up tar and gravel and gyp deck.

If there are any questions, please call Josh Mease at (828) 734-5570.